Northfield Constructions Pvt. Ltd.

Northfield Residency, Tower B · Sector 9, Pune 411057

Bill of Quantities: Windows, Doors and Finishes

Project	Northfield Residency, Tower B
Flat	302 (3 BHK, third floor)
Revision	R2, 14 August 2026

Item	Description	Room	Unit	Qty	Rate (Rs)	Amount (Rs)
A. Windows						
W-1	UPVC openable window, 1200 x 1500 mm	Living Room	nos	3	9,500	28,500
W-2	UPVC openable window, 900 x 1200 mm	Kitchen	nos	1	7,200	7,200
W-3	UPVC openable window, 1200 x 1500 mm	Bedroom 1	nos	2	9,500	19,000
W-4	UPVC openable window, 1200 x 1500 mm	Bedroom 2	nos	4	9,500	38,000
W-5	UPVC openable window, 1200 x 1500 mm	Bedroom 3	nos	2	9,500	19,000
B. Doors						
D-1	Main entrance door, teak veneer flush shutter, 1000 x 2100 mm, with frame, hinges and mortise lock	Living Room	nos	1	24,000	24,000
D-2	Flush door, 900 x 2100 mm, with frame and hardware	Bedroom 1	nos	1	11,500	11,500
D-3	Flush door, 900 x 2100 mm, with frame and hardware	Bedroom 2	nos	1	11,500	11,500
D-4	Flush door, 900 x 2100 mm, with frame and hardware	Bedroom 3	nos	1	11,500	11,500
D-5	Flush door, 800 x 2100 mm, with frame and hardware	Kitchen	nos	1	10,000	10,000
C. Finishes and services						
F-1	Internal cement plaster, 12 mm thick, in two coats	All rooms	sqm	240	380	91,200
F-2	Vitrified floor tiles, 600 x 600 mm, including skirting	All rooms	sqm	96	1,150	1,10,400
F-3	Interior acrylic emulsion paint, two coats over primer	All rooms	sqm	520	140	72,800
E-1	Electrical light and power points, concealed copper wiring	All rooms	nos	42	1,800	75,600
Total, Flat 302						**5,30,200**

Sample document prepared for the SiteProof demo. The builder, project and allottee are fictional.